DOCUMENT NO: ASAP 6006 VERSION: 2021-01-11 Page 1 of 3

TITLE: Part 7 Refuge Alternative Breathable Air Component Approval, Extension

of Approval, and Subsequent Approval, under §7.506

MSHA Mine Safety and Health Administration, Approval & Certification Center

1.0 PURPOSE

The purpose of this Standard Application Procedure (SAP) is to explain the basic investigative process and outline the minimum document requirements necessary to initiate an investigation leading to the issuance of a Refuge Alternative Breathable Air Component Approval, Extension of Approval, or Subsequent Approval under 30 CFR Part 7, §7.506.

2.0 SCOPE

This SAP applies to all applications for Refuge Alternative Breathable Air Component Approval, Extension of Approval, or Subsequent Approval under Part 7, Subpart L, §7.506.

3.0 REFERENCES

This SAP refers to "Application Cancellation Policy", APOL1009.

4.0 **DEFINITIONS**

- 4.1. Approval- A document issued by MSHA which states that a product has met the requirements of this part and which authorizes an approval marking identifying the product as approved.
- 4.2. Extension Of Approval- A document issued by MSHA which states that the change to a product previously approved by MSHA under this part meets the requirements of this part and which authorizes the continued use of the approval marking after the appropriate extension number has been added.
- 4.3. Subsequent Approval A product that is similar to one for which the applicant already holds an approval.

5.0 APPLICATION PROCEDURE

- 5.1. All applications must include the following information:
- 5.1.1. Application Letter Each application letter for approval of a product should include a brief description of the product, and, if appropriate, a

ASAP 6006 2021-01-11.doc

Print Date: 1/28/2021

TITLE: Part 7 Refuge Alternative Breathable Air Component Approval, Extension

of Approval, and Subsequent Approval, under §7.506

MSHA Mine Safety and Health Administration, Approval & Certification Center

statement indicating whether, in the applicant's opinion, testing is required. If testing is not required, the applicant should explain the reasons for not testing. The application letter must be signed by the person responsible for answering any questions regarding the subject application. (Refer to Enclosures A, B, and C for completed samples.)

- 5.1.2. Certified Statement(s), as required by Part 7. (Refer to Enclosure D.)
- 5.1.3. A checklist (Refer to Enclosure E). Submittal of this checklist to MSHA is optional.
- 5.1.4. One copy of all documentation required to show details of the design and construction of the Refuge Alternative Breathable Air Component per 30 CFR, Subpart L, Paragraph 7.506, including test data, test results, calculations, and other information to support how requirements have been met. This documentation is outlined in the checklist, Enclosure E.

Note: Documents previously accepted by the Mine Safety and Health Administration does not need to be submitted, unless modified.

- 5.2. Upon receipt of the application package by the Approval and Certification Center, a fee estimate letter is prepared and sent to the applicant, unless the applicant has a blanket authorization on file. The fee estimate letter includes an estimate of the maximum anticipated fee to complete the investigation and a tentative starting date.
- 5.2.1. An authorization response form is included with the fee estimate. The authorization response form indicates agreement to pay expenses up to the maximum estimated fee for the investigation or requests cancellation of the application. This form must be completed and returned by the applicant before any further action is taken on the application. If the form is not returned within thirty days from the date of the letter, the application is canceled.
- 5.2.2. When unforeseen circumstances encountered during the investigation result in exceeding the estimated fee, the applicant is contacted (either by phone or email) and given the option of canceling the action or accepting the new estimated fee.

Print Date: 1/28/2021

DOCUMENT NO: ASAP 6006 VERSION: 2021-01-11 Page 3 of 3

TITLE: Part 7 Refuge Alternative Breathable Air Component Approval, Extension

of Approval, and Subsequent Approval, under §7.506

MSHA Mine Safety and Health Administration, Approval & Certification Center

- 5.3. During the investigation, applicants are notified if MSHA elects to observe any product testing in accordance with Section 7.4(c), and of any discrepancies or additional information needed to process the application. Applicants are notified by mail and telephone. If an email address is provided, the discrepancy letter may be emailed.
- 5.4. After all the technical documents are evaluated and any changes required as a result of the viewing of any tests and inspection is finalized, the formal Approval, Extension of Approval, or Subsequent Approval letter is issued. An invoice for the total cost of the investigation is sent after final approval issuance.
- 5.5. Submit the application to MSHA by one of the following methods:
- 5.5.1. Mail to: MSHA Approval and Certification Center

Attention: IPSO 765 Technology Drive, Triadelphia, WV 26059

- 5.5.2. FAX to: 304-547-2044
- 5.5.3. Electronically: For information and instructions on setting up an account with MSHA go to:

http://www.msha.gov/techsupp/acc/application/online.htm

Contact the Applied Engineering Division at 304-547-0400 for additional information concerning these procedures.

Print Date: 1/28/2021

(SAMPLE) PART 7 REFUGE ALTERNATIVE BREATHABLE AIR COMPONENT APPROVAL APPLICATION LETTER

Chief, Approval and Certification Center 765 Technology Drive Triadelphia, WV 26059 Company and Address: ABC Air Component, Inc. 2 Starlake Avenue Wheeling, WV 26003

Date: 01-01-2009

Subject: New Approval of the Refuge Alternative Breathable Air Component Model

1XXXX

Company Application Code No.: 123456

Gentlemen:

We are requesting approval of the subject refuge alternative breathable air component built according to drawing 1XXXX-1.

This breathable air component is for a refuge alternative with occupancy up to 15 for 96 hours. The breathable air component is built per drawing 1XXXX-1.

Enclosed are all drawings and specifications pertinent to this application. If there are any questions, please contact John Doe at 304-555-1234.

Sincerely,

John Doe President

(SAMPLE) PART 7 REFUGE ALTERNATIVE BREATHABLE AIR COMPONENT EXTENSION OF APPROVAL APPLICATION LETTER

Chief, Approval and Certification Center 765 Technology Drive Triadelphia, WV 26059 Company and Address: ABC Air Component, Inc. 2 Starlake Avenue Wheeling, WV 26003

Date: 01-01-2009

Subject: Extension of Approval of the Refuge Alternative Breathable Air Component Model 1XXXX Company Application Code No.: 123457

Gentlemen:

We are requesting approval of the subject refuge alternative breathable air component built according to drawing 2XXXX-1.

The subject breathable air component is similar to the breathable air component under 07-LCA09XXXX-0, in that it is rated for 10 persons, for 96 hours, except the existing number of oxygen bottles has been increased by 50%.

Enclosed are all new or revised drawings and specifications pertinent to this application. If there are any questions, please contact John Doe at 304-555-1234.

Testing of this breathable air component is/is not necessary, based on the testing conducted and witnessed by an MSHA representative under Approval 07-LCA 09XXXX-0.

Sincerely,

John Doe President

(SAMPLE) PART 7 REFUGE ALTERNATIVE BREATHABLE AIR COMPONENT SUBSEQUENT APPROVAL APPLICATION LETTER

Chief, Approval and Certification Center 765 Technology Drive Triadelphia, WV 260592

Company and Address: ABC Air Component, Inc. 2 Starlake Avenue Wheeling, WV 26003

Date: 01-01-2009

Subject: Subsequent Approval of the Refuge Alternative Breathable Air Component Model 3XXXX, Company Application Code No.: 123457

Gentlemen:

We are requesting a subsequent approval of the subject breathable air component built according to drawing 1XXXX. The subject breathable air component is similar to the 10 person, 96 hour rated breathable air component built according to drawing 1XXXX-1, Approval No. 07-LCA09XXXX-0, except the rating is being increased to 15 person, 96 hours.

Testing of this breathable air component is/is not necessary, based on the testing conducted and witnessed by an MSHA representative under Approval 07-LCA 09XXXX-0.

Enclosed are all of the new or revised drawings and specifications pertinent to this application. If there are any questions, please contact John Doe at 304-555-1234.

Sincerely,	
John Doe President	

PART 7 REFUGE ALTERNATIVES BREATHABLE AIR COMPONENT CERTIFIED STATEMENTS


Company:	Date:
Address:	
Subject:	
Company Application	on Code No.:
I,(Signature)	, as the responsible company official, hereby certify that:
	e alternative breathable air component will have Quality Assuranc as specified in Title 30 Code of Federal Regulations 30 CFR Part 7,
` '	e alternative breathable air component has been designed to meet l requirements set forth in 30 CFR Part 7, Subpart L (7.504).
()	e alternative breathable air component has been designed to meet able air component criteria set forth in 30 CFR Part 7, Subpart L
` '	e alternative breathable air component has been tested and meets tion of the technical requirements set forth in 30 CFR Part 7, 5) and 7.506).
	e cited in the application is the only change that affects the nts (for subsequent and extensions of approval only)(30 CFR, Part 7.3(f)). (If applicable)
Sincerely,	
John Doe	
President	

PART 7 REFUGE ALTERNATIVE BREATHABLE AIR COMPONENT APPROVAL/ EXTENSION OF APPROVAL/ SUBSEQUENT APPROVAL CHECKLIST

Complete all of the following by adding a checkmark on the lines provided. The checkmark signifies the item has been positively addressed. N/A signifies the item is not applicable to the design of the refuge alternative.

Note: It is strongly recommended that the checklist is included with the application. Providing the document/drawing number where the checklist item is met will further streamline the process. (For example, blast overpressure passing test results, test sheet number 15)

ADMINISTRATIVE



TECHNICAL

APPLICATION REQUIREMENTS (Section 7.503)	Drawing or
	Document No.
An application for approval of a refuge alternative or	
component shall include:	
1. The refuge alternative's or component's make and	
model number, if applicable.(Section 7.503 (a) (1))	
2. A list of the refuge alternative's or component's parts	
that includes: (Section 7.503 (a) (2))	
a. The MSHA approval number for electric-	
powered equipment; (Section 7.503 (a) (2) (i))	
b. Each component's or part's in-mine shelf life,	
service life, and recommended replacement	
schedule; (Section 7.503 (a) (2) (ii))	
c. Materials that have a potential to ignite used	
in each component or part with their MSHA	
approval number (Section 7.503 (a) (2) (iii)); and	
d. A statement that the component or part is	
compatible with other components and upon	
replacement, is equivalent to the original	
component or part (Section 7.503 (a) (2) (iv))	
3. The capacity and duration (the number of persons it is	
designed to maintain and for how long) of the refuge	
alternative or component on a per-person per-hour	
basis. (Section 7.503 (a) (3))	
4. The length, width, and height of the space required for	
storage of each component. (Section 7.503 (a) (4))	
5. A description of the breathable air component,	
including drawings, air-supply sources, piping,	
regulators, and controls.(Section 7.503 (b) (1))	
6. The maximum volume, excluding the airlock; the	
dimensions of floor space and volume provided for	
each person using the refuge alternative; and the floor	
space and volume of the airlock.(Section 7.503 (b) (2))	
7. The maximum positive pressures in the interior space	
and the airlock and a description of the means used to	
limit or control the positive pressure.(Section 7.503 (b)	
(3))	
8. The maximum allowable apparent temperature of the	
interior space and the airlock and the means to control	
the apparent temperature. (Section 7.503 (b) (4))	

9. The maximum mine air temperature under which the refuge alternative is designed to operate when the unit	Drawing or Document No.
is fully occupied. (Section 7.503 (b) (5))	
10. Drawings that show the features of each component	
and contain sufficient information to document	
compliance with the technical requirements. (Section	
7.503 (b) (6))	
11. A manual that contains sufficient detail for each	
refuge alternative or component addressing in-mine	
transportation, operation, and maintenance of the unit.	
(Section 7.503 (b) (7))	
12. A summary of the procedures for deploying refuge	
alternatives. (Section 7.503 (b) (8))	
13. A summary of the procedures for using the refuge	
alternative. (Section 7.503 (b) (9))	
14. The results of inspections, evaluations, calculations,	
and tests conducted under this subpart. (Section 7.503	
(b) (10))	
REFUGE ALTERNATIVES AND COMPONENTS;	
GENERAL REQUIREMENTS. (Section 7.504)	
GENERAL REQUIREMENTS (SECTION 7.501)	
Refuge alternatives and components:	
1. Electrical components that are exposed to the mine	
atmosphere, shall be approved as intrinsically safe for	
use. Electrical components located inside the refuge	
alternative shall be either approved as intrinsically	
safe or approved as permissible (Section 7.504 (a) (1))	
2. Shall not produce continuous noise levels in excess of	
85 dBA in the structure's interior. (Section 7.504 (a) (2))	
3. Shall not liberate harmful or irritating gases or	
particulates into the structure's interior or airlock.	
(Section 7.504) (a) (3))	
4. Shall be designed so that the refuge alternative can be	
safely moved with the use of appropriate devices such	
as tow bars. (Section 7.504 (a) (4))	
5. Shall be designed to withstand forces from collision of	
the refuge alternative structure during transport or	
handling. (Section 7.504 (a) (5))	

The apparent temperature in the structure shall be controlled as follows:	Drawing or Document No.
 6. When used in accordance with the manufacturer's instructions and defined limitations, the apparent temperature in the fully occupied refuge alternative shall not exceed 95 degrees Fahrenheit (°F). (Section 7.504 (b) (1)) 7. Tests shall be conducted to determine the maximum apparent temperature in the refuge alternative when used at maximum occupancy and in conjunction with required components. Test results, including calculations, shall be reported in the application. (Section 7.504 (b) (2)) 	
The refuge alternative shall include:	
 8. A two-way communication facility that is a part of the mine communication system, which can be used from inside the refuge alternative; and accommodations for an additional communication system and other requirements as defined in the communications portion of the operator's approved Emergency Response Plan. (Section 7.504 (c) (1)) 9. Lighting sufficient for persons to perform tasks; (Section 7.504 (c) (2)) 10. A means to contain human waste effectively and minimize objectionable odors; (Section 7.504 (c) (3)) 11. First aid supplies; (Section 7.504 (c) (4)) 12. Materials, parts, and tools for repair of components; (Section 7.504 (c) (5)) and 13. A fire extinguisher that: a. Meets the requirements for portable fire extinguishers used in underground coal mines under part 75; (Section 7.504 (c) (6) (i)); b. Is appropriate for extinguishing fires of chemicals used for harmful gas removal; (Section 7.504 (c) (6) (ii)) and c. Uses a low-toxicity extinguishing agent that does not produce a hazardous by-product when deployed. (Section 7.504 (c) (6) (iii)) 	

Containers used for storage of refuge alternative components	Drawing or
or provisions shall be:	Document No.
14. Airtight, waterproof, and rodent-proof (Section 7.504	
(d) (1))	
15. Easy to open and close without the use of tools;	
(Section 7.504 (d) (2)) and	
16. Conspicuously marked with an expiration date and	
instructions for use. (Section 7.504 (d) (3))	
FLASH FIRE INSPECTION (Section 7.505)	
1. An inspection shall be conducted to determine that a	
1. An inspection shall be conducted to determine that a	
flash fire of 300°F for 3 seconds does not prevent the stored components from operating; (Section 7.505 (b)	
(5))	
(3))	
BREATHABLE AIR COMPONENTS (Section 7.506)	
1. Breathable air shall be supplied by compressed air	
cylinders, compressed breathable-oxygen cylinders, or	
boreholes with fans installed on the surface or	
compressors installed on the surface. Only	
uncontaminated breathable air shall be supplied to the	
refuge alternative. (Section 7.506 (a))	
Machanisms shall be averided and averadewas shall be	
Mechanisms shall be provided and procedures shall be included so that, within the refuge alternative (Section 7.506	
(b))	
2. The breathable air sustains each person for 96 hours,	
(Section 7.506 (b) (1))	
3. The oxygen concentration is maintained at levels	
between 18.5 and 23 percent, (Section 7.506 (b) (2)) and	
4. The average carbon dioxide concentration is 1.0 percent	
or less and excursions do not exceed 2.5 percent.	
(Section 7.506 (b) (3))	
5. Breathable air supplied by compressed air from	
cylinders, fans, or compressors shall provide a	
minimum flow rate of 12.5 cubic feet per minute of	
breathable air for each person. (Section 7.506 (c))	

Fans or compressors shall meet the following: (Section 7.506	Drawing or
(c) (1))	Document No.
6. Be equipped with a carbon monoxide detector	
located at the surface that automatically provides a	
visual and audible alarm if carbon monoxide in	
supplied air exceeds 10 parts per million (ppm).	
(Section 7.506 (c) (1) (i))	
7. Provide in-line air-purifying sorbent beds and filters or	
other equivalent means to assure the breathing air	
quality and prevent condensation, and include	
maintenance instructions that provide specifications	
for periodic replacement or refurbishment. (Section	
7.506 (c) (1) (ii)	
8. Provide positive pressure and an automatic means to	
assure that the pressure is relieved at 0.18 psi, or as	
specified by the manufacturer, above mine	
atmospheric pressure in the refuge alternative.	
(Section 7.506 (c) (1) (iii)	
9. Include warnings to assure that only uncontaminated	
breathable air is supplied to the refuge alternative.	
(Section 7.506 (c) (1) (iv)	
10. Include air lines to supply breathable air from the fan	
or compressor to the refuge alternative. (Section 7.506	
(c) (1) (v)	
a. Air lines shall be capable of preventing or	
removing water accumulation. (Section	
7.506 (c) (1) (v) (A)	
b. Air lines shall be designed and protected to	
prevent damage during normal mining	
operations, a flash fire of 300°F for	
3 seconds, a pressure wave of 15 psi	
overpressure for 0.2 seconds, and ground	
failure. (Section 7.506 (c) (1) (v) (B)	
11. Assure that harmful or explosive gases, water, and	
other materials cannot enter the breathable air.	
(Section 7.506 (c) (1) (vi)	
12. Redundant fans or compressors and power sources	
shall be provided to permit prompt re-activation of	
equipment in the event of failure. (Section 7.506 (c) (2)	
equipment in the event of failure. (Section 7.500 (c) (2)	
Compressed breathable oxygen shall – (Section 7.506 (d))	
13. Include instructions for deployment and operation;	
(Section 7.506 (d) (1))	

14.	Provide oxygen at a minimum flow rate of 1.32 cubic	Drawing or
	feet per hour per person; (Section 7.506 (d) (2))	Document No.
15.	Include a means to readily regulate the pressure and	
	volume of the compressed oxygen; (Section 7.506 (d)	
	(3))	
16.	Include an independent regulator as a backup in case	
	of failure; (Section 7.506 (d) (4)) and	
17.	Be used only with regulators, piping, and other	
	equipment that is certified and maintained to	
	prevent ignition or combustion. (Section 7.506 (d)	
	(5))	
18.	The applicant shall prepare and submit an analysis or	
	study demonstrating that the breathable air	
	component will not cause an ignition. (Section 7.506	
	(e))	
	a. The analysis or study shall specifically	
	address oxygen fire hazards and fire	
	hazards from chemicals used for removal of	
	carbon dioxide. (Section 7.506 (e) (1))	
	b. The analysis or study shall identify the	
	means used to prevent any ignition source.	
	(Section 7.506 (e) (2)	
A DDD OX7	AL MARKINGO (C. C. FEOO)	
APPROV	AL MARKINGS (Section 7.509)	
1 1	ach approved refuse alternative or component shall	
	ach approved refuge alternative or component shall	
	be identified by a legible, permanent approval	
	narking that is securely and conspicuously attached	
	the component or its container. (Section 7.509 (a))	
	he approval marking shall be inscribed with the omponent's MSHA approval number and any	
	dditional markings required by the approval.	
	Section 7.509 (b))	
,	The refuge alternative structure shall provide a	
	onspicuous means for indicating an out-of-service	
	tatus, including the reason it is out of service. (Section	
	(.509 (c))	
	The airlock shall be conspicuously marked with the	
	ecommended maximum number of persons that can	
	use it at one time. (Section 7.509 (d))	